

工 事 数 量 総 括 表

[illegible]

[illegible][illegible]

土量配分計算書

掘 削	種 別		土 量
	掘削片切り	土砂	549.3
	掘削オーブン	土砂	2,836.5
	合 計		3,385.8

V= 3,385.8 流用

盛 土	種 別	土 量
	路床盛土	0.0
	路体盛土	0.0
	路体外盛土	0.0
	歩道盛土	0.0
	路肩盛土	0.0
	畦畔	0.0
	合 計	0.0

流用可能土	盛土	残土
3,385.8	-(0.0 / 0.9) =	3,385.8

作業土工	種 別	土 量
床 堀	水路工	0.0
	擁壁工	0.0
	合 計	0.0
埋 戻	水路工	0.0
	擁壁工	0.0
	合 計	0.0

残土		
本 線	3,385.8	3,385.8
作業土工	0.0	
		残土計 3,385.8
軟弱層除去		0.0

作業土工	残土処理	0.0	-(0.0 / 0.9) =	0.0
------	------	-----	------------------	-----

掘 削	種 別	土 量
	軟弱層除去 粘性土	0

道路土工-1							
測 点	距 離	C1土砂掘削 片切掘削			C2土砂掘削 オープン掘削		
		断面積	平均断面	立米	断面積	平均断面	立米
NO. 5+10. 0		4. 7	2. 35		3. 7	1. 85	
NO. 6	10. 000	4. 5	4. 60	46. 0	0. 0	1. 85	18. 5
NO. 6+14. 0	14. 000	43. 8	24. 15	338. 1	5. 2	2. 60	36. 4
NO. 7	6. 000	2. 6	23. 20	139. 2	64. 0	34. 60	207. 6
NO. 8	20. 000	0. 0	1. 30	26. 0	193. 4	128. 70	2, 574. 0
小計	50. 000			549. 3			2, 836. 5
計	50. 000			549. 3			2, 836. 5

道路土工-10							
測 点	距 離	切土法面整形 土砂片切(左)			切土法面整形 土砂片切(右)		
		長さ	平均長	平米	長さ	平均長	平米
NO. 5+10. 0		0. 7	0. 35		0. 0	0. 00	
NO. 6	10. 000	1. 6	1. 15	11. 5	6. 2	3. 10	31. 0
NO. 6+14. 0	14. 000	0. 0	0. 80	11. 2	15. 8	11. 00	154. 0
NO. 7	6. 000	0. 0	0. 00	0. 0	2. 0	8. 90	53. 4
NO. 8	20. 000	0. 0	0. 00	0. 0	0. 0	1. 00	20. 0
小計	50. 000			22. 7			258. 4
計	50. 000			22. 7			258. 4

道路土工-11							
測 点	距 離	切土法面整形 土砂オフン(左)			切土法面整形 土砂オフン(右)		
		長さ	平均長	平米	長さ	平均長	平米
NO. 5+10. 0		0. 0	0. 00		1. 4	0. 70	
NO. 6	10. 000	0. 0	0. 00	0. 0	0. 0	0. 70	7. 0
NO. 6+14. 0	14. 000	0. 0	0. 00	0. 0	1. 5	0. 75	10. 5
NO. 7	6. 000	0. 0	0. 00	0. 0	13. 2	7. 35	44. 1
NO. 8	20. 000	0. 0	0. 00	0. 0	19. 2	16. 20	324. 0
小計	50. 000			0. 0			385. 6
計	50. 000			0. 0			385. 6

法面工数量総括表

[illegible]

道路法面工-1							
測 点	距 離	植生基材吹付(左)			植生基材吹付(右)		
		長さ	平均長	平米	長さ	平均長	平米
NO. 5+10. 0		0. 0	0. 00		0. 0	0. 00	
NO. 6	10. 000	0. 2	0. 10	1. 0	4. 8	2. 40	24. 0
NO. 6+14. 0	14. 000	0. 0	0. 10	1. 4	17. 4	11. 10	155. 4
NO. 7	6. 000	0. 0	0. 00	0. 0	15. 3	16. 35	98. 1
NO. 8	20. 000	0. 0	0. 00	0. 0	23. 4	19. 35	387. 0
小計	50. 000			2. 4			664. 5
計	50. 000			2. 4			664. 5